

# AIR CALIBRE SYSTEMS

Specialists in Clean Room Technology C.A.  
ISO 9001:2015 Certified Company  
GSTN: 33ABAF1646F1Z1  
SAC: 998346



**Quotation# Q2399**

**Date: 09/02/2026**

M/s. MELMARUVATHUR ADHIPARASAKTHI INSTITUTE OF MEDICAL SCIENCES AND RESEARCH  
GST Road,, , Melmaruvathur, tamilnadu - 603319

**Kind Attn: The Medical Director <br>MAPIMS Hospital**

Dear Sir/Madam,

**Sub: Quotation for Supply of Bio Safety Cabinet Class II B2**

As per your phone discussion we have submit our best quote for your kind approval.

S.No	Description	Qty/Day	Rate (Rs.)	Amount (Rs.)
1	BIO SAFETY CABINET - SS 304 * Model " Lab protects ACS-12	1.00	169492.00	169492.00
			<b>Total</b>	<b>169492.00</b>
			<b>GST (18%)</b>	<b>30508.56</b>
			<b>Net Amount</b>	<b>200000.56</b>

**Note: TECHNICAL SPECIFICATION:**

<br>\* Cleanliness Level - ISO CLASS 100 as per ISO 14644-1

<br>\* Direction of Flow - Vertical

<br>\* Air Balancing 100% exhaust(B2)

<br>\* Virus tight extract HEPA filter(B2)

<br>\* Virus burn out unit(B2) " will be charge extra

<br>\* Particle Retention - 0.3 Micron & above

<br>\* Inflow Velocity - 100 FPM  $\hat{\pm}$  20%

<br>\* Down Flow Velocity - 90 FPM  $\hat{\pm}$  20%

<br>\* Noise level 65 decibel on " scale  $\hat{\pm}$  5

<br>\* Pressure Differential 0 - 25 mm Magnehelic Gauge

<br>\* Ultra violet lamp PHILIPS - make Illumination Fluorescent tube / LED fittings

<br>\* Standard Accessories Additional power point 5 /15 Amps " 2 Nos.

<br>\* Air/Gas inlet nozzle, Floor levelling screws & wire chord etc

<br>\* Material of Construction: The Complete Cabinet in SS 304 construction

<br>\* HEPA Filter: Media Ultra clean glass fiber paper " imported

<br>\* Magnahelic gauge Pressure Differential 0 - 25 mm

<br>\* Supply Air & Exhaust Type Mini-Pleated constructions Retention 0.3 Micron Efficiency 99.97% \* <br>\* Pressure drop 12 mm WG

<br>\* Grade H13 rating

<br>\* Note: Virus Burnout Unit will be in built on Biosafety cabinet at no extra cost.

<br>\* 4 ft. Base stand with leg levelers, 30" work surface height

<br> Packing & Forwarding - NIL

**Terms & Conditions:**

- Payment: 100% advance
- Scope:

# AIR CALIBRE SYSTEMS

Specialists in Clean Room Technology C.A.  
ISO 9001:2015 Certified Company  
GSTN: 33ABAF1646F1Z1  
SAC: 998346



---

Packing & Forwarding: 5% Extra

Delivery: Approximately 2 to 4 week's time, Actual delivery time will be notified separately

Freight: To pay

Warranty : 12 months

Offer validity : 1 month

Others : Civil work, Plumbing & Electrical works should be taken care by the customer if required.

We sincerely hope you find our quote to be of interest and in line with your requirement and look forward to your valued order at the earliest.

Thanking you,  
Yours faithfully,

**M P Madan**  
**Customer Support Manager**  
**90430 22768**